

## Step 1

Lay one of the shelf panels on the floor and insert **Leg Stackers** over outside sockets as shown.

## Step 2

Invert the next level panel and insert **24**" **posts** into the sockets as shown.

## Step 3

Return panel with the **24**" **posts** to upright position. Align posts over **Leg Stackers** and push all the way down until leg stackers are inserted into posts. Repeat steps **1** through **3** for multi-shelf configurations.



 3401 Chief Drive - Holly, Michigan 48442-9333 - Phone (810) 953-9400 - Fax (810) 953-9440
 1-800-523-6899

 s3616\_inst/0112
 Copyright © 2012 All rights reserved.